Issued: October 16, 2008

Northwest Clean Air Agency (NWCAA) hereby issues Order of Approval to Construct (OAC) #1030

Project Summary: Remove Stage II gasoline vapor recovery equipment as allowed under NWCAA 580.6 and WAC 173-491-040.

APPLICANT

Amanda Muscavage
Naval Air Station Whidbey Island
Seaplane Base
2110 North Coral Sea Avenue
Oak Harbor, WA 98278

OWNER

Department of Defense
United States of America

FACILITY LOCATION:

2110 North Coral Sea Avenue (Seaplane Base) Oak Harbor, WA 98278

As authorized by Northwest Clean Air Agency Regulation Section 300, this order is issued subject to the following restrictions and conditions:

You are hereby granted approval to remove stage II equipment subject to the following conditions:

1. Order of Approval to Construct (OAC) No. 1030 supersedes and cancels OAC No. 710 dated September 1, 1999.

2. The stage 1 equipment shall be continuously maintained and operated in a vapor tight manner in accordance with state and local rules as defined in WAC 173-491 and NWCAA section 580.

3. Stage 1 equipment shall be maintained and operated in good working condition. This includes but is not limited to:
   - Keeping all protective caps on tight and in the locked position.
   - Maintaining all sealing gaskets and poppet valves in good condition.
   - Assuring vapor return hoses are attached and operated in a leak tight manner during fuel deliveries.
   - Using all reasonable necessary measures to prevent spilling, discarding in sewers, storing in open containers or handling of fuel in a manner that will result in evaporation to the ambient air.

Annie Naismith, PE Permitting Engineer	Mark Buford, PE Reviewing Engineer	Lynn Billington, PE Director, Engineering Dept.